

# J-PARC Accelerator and Slow Extraction


Masahito Tomizawa

Main Ring Group  
KEK Acc. Lab.

- Linear Accelerator (Linac)
- Rapid Cycle Synchrotron (RCS)
- Main Ring (MR)
- Slow Extraction from Main Ring


Thanks M. Ikegami (linac), M. Kinsho (RCS) for their helps

# J-PARC Facility



## Phase I

- First stage
  - Linac 181MeV, 30mA, 25Hz
  - RCS 3GeV, 0.6MW
  - MR 30GeV, 400kW (fast)
- Next Stage
  - Linac 400MeV, 50mA, 25Hz
  - RCS 3GeV, 1.0MW
  - MR 30GeV, 670kW (fast)




## Phase II

- MR 50GeV, 750kW
- Extension of Hadron and Neutron Facility
- Nuclear Transmutation Facility(ADS)
  - Linac 600MeV, 50Hz

# First Stage Linac parameters

- beam:  $\text{H}^-$
- Energy: 181 MeV
- Peak current: 30 mA
- Repetition: 25 Hz
- Pulse width: 0.5 msec
- Chopper rate: 56%
- Beam current:  $200\mu\text{A}$
- Beam power: 36kW

IS: Ion Source  
RFQ: Radio Frequency Quadrupole linac  
DTL: Drift Tube Linac  
SDTL: Separate-type DTL  
ACS: Annular Coupled Structure linac



# Linac Beam Commissioning


- RUN1 (Nov. 2006): RFQ : 3MeV, 30mA, 50 $\mu$ s, 5Hz
- RUN2 (Dec. 2006): DTL1 (19.7MeV), delivered to 0 degree dump
- RUN3 (Jan. 2007): SDTL (181MeV), delivered to 30 degree dump
- RUN4 (Feb. 2007): Government inspection for radiation safety
- RUN5 (Mar. 2007): SDTL fine rf phase scan (5mA, 120W)
- RUN6 (Apr. 2007): transverse matching (5mA, 120W)



Commemorative photo on Jan. 24, 2007

# Linac Beam Commissioning


- May-Jun 2007 181MeV, 600W  
(30mA, 50  $\mu$ s, 2Hz)
- Sep. 2007- $\rightarrow$  beam delivery to RCS




# Rapid Cycle Synchrotron (RCS)

- Rapid Cycle (25Hz)
- Ceramics vacuum chamber
- stranded conductor coil for D,Q magnets
- High field MA loaded cavity
- long lived carbon foil for charge exchange injection

• Circumference	348.3m
• Repetition	25Hz(40ms)
• Injection Energy	180/400 MeV
• Output Energy	3GeV
• Beam Power	0.6/1MW
• Harmonic	2
• Bunch Number	2
• Nominal Tune	(6.72, 6.35)
• Transition $\gamma_t$	9.14
• S.C. Tune Shift	-0.2



# RCS Main Tunnel Status





## RCS Recent Progress

- All of RF cores have been successfully high-power tested and all cavities have been installed by last week
- 7-family quadrupoles and a bending resonant networks have been successfully excited up to full current (3GeV).


## RCS Schedule

- The remaining of injection/extraction, vacuum and monitor components will be soon installed
- Off beam commissioning  
(checking total hardware/control system without beam)  
--> Aug. 2007
- First Beam commissioning  
--> Sep. 2007-Feb.2008  
3GeV, 4kW beam power

# RCS resonant network and power supply for QM

60 QM are excited in 7 independent resonant networks.


- (1) The power supply provided both AC and DC components simultaneously is inserted in series by halving one of the resonant meshes.
- (2) The QM networks consist of 3 or 6 meshed each



**Power Supply**  
 Voltage : 1200 Vp  
 Current : 1180 Ap  
 Rating : 193 kW



**Resonant Capacitor**  
 Voltage : 3587 Vp  
 Capacitance : 1740 mF  
 Mass : 12 ton



Current waveform (QFM power supply)

**Choke Transformer**  
 Type : All-in-one  
 Inductance : 144 mH  
 Mass : 29 ton


**Q magnet**



# Main Ring (MR)


- Imaginary Transition  $\gamma$
- High Gradient Magnetic Alloy loaded RF cavity
- Small Loss Slow Extraction Scheme
- Both Side Fast Extraction for Neutrino and Abort line
- hands on maintenance scheme for small radiation exposure

- Injection Energy 3GeV
- Output Energy 30GeV (slow)  
30GeV (fast)  
50GeV (Phase II)
- Circumference 1567.5m
- Beam Power 0.75MW (Phase II)
- Repetition 0.3Hz
- Harmonic 9
- Bunch Number 8
- Nominal Tune (22.4, 20.8)



# MR tunnel

- |                            |   |                                 |
|----------------------------|---|---------------------------------|
| 1. Magnet installation     | → | Arc-A,C,B, 3-50BT almost finish |
| 2. Vacuum • BPM            | → | Arc-C center, Arc-B center      |
| 3. Alignment               | → | Arc-B, C finish                 |
| 4. Power supply (D3,D2,D1) | → | D3(50%)、D2(30%)、D1 (50%)        |
| 5. Wiring                  | → | just start at BT                |



BT collimator



BT near to MR



## MR Status (except for slow extraction)


- Installation, cabling are on schedule.
  - Fast extraction kickers: electric discharge and slow rise time under repairing to make round corners for ferrite cores  
 $1.1\mu\text{s} \rightarrow 1.6\mu\text{s}$  (h=9: 8banches  $\rightarrow$  6banches)
- Fast extraction thin magnetic septa:  
ceramic collars to fix conductors were broken  
under repairing

## MR Schedule (except for slow extraction)

- Off beam commissioning (check of total system without beam)  
 $\rightarrow$  Dec. 2007-Apr. 2008
- Beam commissioning
  - (1) May-Jun 2008  
3GeV, 0.1kW beam power
  - (2) Dec. 2008-Feb. 2009  
Acceleration


# Slow Extraction from Main Ring

- Slow Beam Extraction at highest Beam intensity
- Small Beam loss design and operation are crucial from radiation
- Good spill quality




- Design of Beam Optics scheme
  - high  $\beta$ , zero dispersion at ESS
  - full chromaticity correction
  - dynamic bump scheme
  - optimum phase angle between ESS and first MS
- Development of ESS and MS
  - with thin septum at enough kick angle
  - > Beam simulation predicts beam loss less than 1%
- Maintenance scenario
  - Remote handling, quick connection/disconnection


ESS(2)




SM10(1)




SM11(1)




SM2(4)



SM30-31(2)




SM32-33(2)




Resonant Sextupoles(8)



Bump magnets (4)



Spill quadrupoles (under design)





# ESS R&D (half length model)

- W(Re3%) 80 $\mu$ m wire type: 170kV/25mm gap -->success!
- W(Re26%) 30 $\mu$ m ribbon type: 170kV/25mm gap -->success!  
--> great progress to reduce beam loss

## Ribbon type

Tension 1kg

061204c.dat






# Magnetic septa R&D

Development of critical parts and current excitation tests

1.5mm conductor (SM1)



SM2 magnet assemblies




7.5mm conductor (SM2)  
SUS tube in copper by HIP






# slow extraction pattern and beam spill

30GeV  
(h=9)



goal  
330-180 kW (180MeV Linac)  
540-300 kW (400MeV Linac)



## Slow Extraction Schedule

- Fabrications of slow extraction components (ESS, Magnetic septa, Bumps, p.s.)  
Fy. 2007
- Installation and off-beam commissioning of above components  
Jul.-Nov. 2008  
(during MR first beam commissioning, temporal vacuum ducts are put instead of these components)
- first slow extraction beam commissioning (30GeV, 1.2 kW beam power)  
Dec. 2008 <--> Feb. 2009
- Fabrications of spill feedback system ( control board, quadrupoles and p.s.)  
Fy. 2008
- spill feedback beam commissioning  
beam commissioning for higher beam intensity  
Sep. 2009 -->

## Concluding Remarks

- J-PARC accelerator is a huge complex system to produce highest proton beam power. All are new system !
- Linac beam has been successfully accelerated to 181 MeV. Beam commissioning for RCS and MR will soon start (this year and next year)
- Reducing beam loss is crucial for high intensity proton machine.

At Day-1 (low beam power),  
establishment of beam handling and stability/reliability for hardware

Beam intensity can be increased step by step for final goal  
within permitted beam loss.

- J-PARC accelerator is multi-purpose machine, should be responsible for various experimental requirements in future.