

Commissioning Experience at SLAC Linac Coherent Light Source (LCLS)


Commissioning Session

Workshop on Accelerator Operations 2010

Michael Stanek

Deputy Head, Accelerator Operations and Safety Division
SLAC National Accelerator Laboratory

Stanford Linear Accelerator Center




- Operated by Stanford University for the U.S. Department of Energy.
- Approximately 1400 employees.
- 3000 users from universities and other labs world-wide.
- Established in 1962 to study high energy particle physics.

SLAC past

- High Energy and Particle Physics
 - 1966: 20+ GeV e- Fixed Target
 - 1972: 3 GeV e-/e+ Colliding beam storage ring (SPEAR ring → J/Psi particle)
 - 1980-1989: 14 GeV e-/e+ (PEP ring)
 - 1989-1998: 50 GeV e-/e+ SLAC Linear Collider (Z_0)
 - 1999-2008: PEP2 “B-factory” 9 GeV e- on 3 GeV e+ colliding beam storage rings

Latest addition: LCLS



~\$300 M Project

LCLS X-ray FEL key elements

Low emittance RF Photo-cathode Injector

- 250 pC \rightarrow 1 nC
- 30 \rightarrow 120 pulse/sec

4.0 -13.6 GeV electron Linac


- Multi-stage bunch compression
- sub-picosecond electron bunches

130 meters of Undulator magnets


Coherent X-ray pulses

\rightarrow 0.8 – 8.0 KeV, $<$ 100 fsec, 3 mJ/pulse

Self-Amplified Spontaneous Emission (SASE)



The electron beam and its synchrotron radiation are so intense that the electron motion is modified by the electromagnetic fields of its own emitted synchrotron light. Under the influence of both the undulator and its own synchrotron radiation, the electron beam begins to form micro-bunches,  separated by a distance equal to the wavelength of the emitted radiation.




X-rays for Material Science


- High brightness, ultra-fast, ultra-small X-ray pulses
 - 800 nm – 1.5 Å wavelength
 - Probe for Atomic, Molecular & Optical Science
 - X-ray Pump-Probe experiments
 - Coherent X-ray imaging
 - Matter in Extreme Conditions

RF Photo-Cathode Gun

- $Q = 1 \text{ nC}$
- $f = 120 \text{ Hz}$
- $G = 120 \text{ MV/m}$
- $\gamma\epsilon_{x,y} = 1 \text{ }\mu\text{m}$
- $\Delta\tau = 10 \text{ ps}$
- $I = 100 \text{ A}$
- $E = 6 \text{ MeV}$




Injector Layout




Use 1 km of existing Linac

SLAC Linac




- Legacy infrastructure & control system
- Some upgrades:
 - 2 bunch compression chicanes.
 - New BPM instrumentation
 - Magnet power supplies

LCLS Accelerator and Compressor Schematic



New Civil Construction & Beamlines

- Beam Transport Hall (above ground)
- Undulator Hall (underground)
 - Tunnel under hill for temperature stability
 - Air temp +/- 0.5 deg C for Undulator field quality
 - 33 Undulator Magnet girders
 - 3.4 m long
 - Integrated diagnostic instrumentation
 - BPM, Wire, Motion Control, Alignment
- Beam Dump
- Front End Enclosure (X-ray diagnostics)



Beam Finder Wire (BFW)
Cavity BPM ($<0.5 \mu\text{m}$)
Quadrupole magnet

3.4-m undulator magnet

sand-filled, thermally isolated supports

beam direction


X-translation (in/out)

Wire Position Monitor

Hydraulic Level System


CAM-based 5-DOF motion control

- Beam Transport Hall
- Undulator Hall
- Electron Beam Dump
- Front End Enclosure
- Near Experimental Hall
- X-Ray Transport Tunnel
- Far Experimental Hall



New X-ray user facilities

2 soft X-ray &
4 hard X-ray hutches



Remodeled Control Room

(see talk – P. Schuh - Control Room and Ergonomics session)





Commissioning Time-Line

- Commissioning
- Project Milestones
- Installation Periods



First FEL Light




Success!

- First X-rays - April 2009
- Front End Enclosure & 1st Hutch – Sept 2009
- First X-ray user experiment – Sep-Dec 2009

- 2nd user Hutch planned May 2010
 - Alternate users every 12 hours

Undulator 'Taper Scan' Shows 1.1 mJ of X-rays



1.5 Å

Pixel sum of x-ray
YAG screen CCD
camera vs undulator
K-taper

4.6 MeV at 0.25 nC
= 1.1 mJ or
 0.8×10^{12}
photons/pulse (15
GW at 75-fs FWHM
pulse length)

Dog-Leg BPMs


Dumpline
BPMs

← ~100 meters →


Beam-Based Undulator Alignment

- Measure undulator trajectory at 4 energies (4.3, 7.0, 9.2, & 13.6 GeV)
- Scale all linac & upstream transport line magnets each time
- Do not change **anything** in the undulator
- Calculate... (*Matlab* GUI)
- Move quads and adjust BPM offsets for dispersion free trajectory
- Iterate...

H. Loos




Undulator Gain Length Measurement at 1.5 Å




What has worked well?

- Dedicated, organized Commissioning team
 - Paul Emma, et.al.
- Early Operator involvement
 - Lectures from System Experts
 - Assist commissioning team on shift
 - Share control room with PEP2 operation
 - (until PEP2 shutdown 2008)
 - Experienced PEP2 operations organization
 - Clearly defined roles, responsibilities

Detailed Staged Commissioning Plan



Task Name		Duration	Start
3	Injector Commissioning	478 days	Thu 6/1/06
1	+ RF Gun Preparation	139 days	Thu 6/1/06
22	+ Pre-Beam Checkout of Injector beamline	41 days	Mon 11/6/06
42	+ Injector beamline commissioning	197.25 days	Tue 12/19/06
43	+ First-pass commissioning/beam to SAB	26 days	Tue 12/19/06
44	+ Set Laser/RF Timing	4 days	Tue 12/19/06
49	+ Transport beam through GTL to YAG02	4 days	Sat 12/23/06
54	+ Transport beam into BXG dump	4 days	Wed 12/27/06
59	+ Transport beam to BXS dump	8 days	Sun 12/31/06
78	+ Time diagnostics	4 days	Mon 1/8/07
87	+ Timing and linac gradient calibration	2 days	Fri 1/12/07
92	Rough steer with BPMs in full injector	1 day	Sun 1/14/07
93	Beam ready for transport to BC1 dump	0 days	Sun 1/14/07
96	+ Second-pass commissioning/characterization	44.5 days	Mon 2/19/07
97	+ Gun and Solenoid characterization	17 days	Mon 2/19/07
104	+ Feedback and diagnostics commissioning	30.5 days	Wed 2/21/07
111	+ 135MeV beam characterization	27.5 days	Thu 3/8/07
136	Injector beam characterized	0 days	Wed 4/4/07
138	+ Third-pass commissioning/machine studies	33 days	Fri 6/1/07
139	+ third pass 6MeV beam characterization	5 days	Fri 6/1/07
162	+ Optimization of 200pC configuration	12 days	Fri 6/1/07
170	+ Optimization of Highest "stable charge" config.	21 days	Wed 6/13/07
179	Injector optimization complete	0 days	Wed 7/4/07
181	+ 2008 Injector re-commissioning	15 days	Sun 10/28/07
4	Linac Commissioning	510.02 days	Fri 11/17/06
2	+ Pre-Beam Checkout to TD11 (after BC1)	7 days	Fri 11/17/06
10	+ Beam to TD11 stopper (after BC1)	180.25 days	Mon 1/15/07
13	+ First Pass Commissioning/beam to TD11	35 days	Mon 1/15/07
14	+ Establish beam on TD11	7.5 days	Mon 1/15/07
25	+ Verify Optics, Calibrate, and Phase	27.5 days	Mon 1/22/07
52	Linac beam ready on TD11	0 days	Sun 2/18/07
54	+ Second Pass Commissioning/characterization	57.75 days	Wed 4/4/07
55	+ Minimize DL1 energy spread	1 day	Wed 4/4/07
57	Study BL11 CSR monitor	3 days	Thu 4/5/07
58	Linac access to fix problems	2 days	Sun 4/8/07
59	+ Setup DL1 launch feedback	2.88 days	Tue 4/10/07
64	+ Setup energy feedback on L0/DL1	3.13 days	Fri 4/13/07
72	+ Setup longitudinal feedback on L1/BC1	6.25 days	Mon 4/16/07
77	Linac access to fix problems	2 days	Sun 4/22/07
78	+ Setup longitudinal feedback on L1/BC1	3.25 days	Tue 4/24/07
83	Test TCAV0 bunch-length meas. software	3 days	Sat 4/28/07
84	Beam-base align critical quadrupoles	1 day	Tue 5/1/07
85	Center CE11 collimator in BC1	2 hrs	Wed 5/2/07
86	Record machine stability (traj, charge, etcx)	8 hrs	Wed 5/2/07



Commissioning Definition and Strategy

All components installed, aligned, connected, and initially verified by the system engineer, then commissioning starts.

Commissioning Sequence (1-4)

1. Pre-Beam Checkout (tunnel and MCC)

- Controls/software testing, check cameras, 'snail' hunt, etc
- Magnet polarities, cable connections, verify motion-control, etc

2. Beam-based Hardware and Software Checkout

- Establish beam transport, RF setup, MPS/BCS tests, etc
- Checkout of all wires, screens, BPMs, toroids, magnets, etc

3. First-Order Optics: Measurement and Correction

- Steering, transmission, oscillation data, feedback setup, etc
- Beta and dispersion matching, beam-base align key quads, etc

4. Full Beam Characterization: Measurement and Correction

- Measure emittance, energy spread, distributions - correct
- Measure beam sensitivities, optimize tuning, beam experiments

No (serious) emittance measurements until all hardware/software checked out!

LCLS Injector Commissioning Day

24-Hour Cycle (7 days/week, 1/2/07 to 9/1/07, 32 total weeks)

DAY SHIFT (8:00-16:00)

1 lead physicist, 1 physicist,
1 controls eng.,
1 LCLS operator, 1 laser operator

After PEP2-BaBar ended (2008),
Full attention of Operations crew
2-3 Ops, 1 Engineering op

SWING SHIFT (16:00-24:00)

1 lead physicist, 1 physicist,
1 LCLS operator, 1 laser op on-call

OWL SHIFT (0:00-8:00)

1 LCLS operator, 1 laser op on-call

Communication & Teamwork

- Accelerator Physicist – Operator handoff
 - Owl Shift left to operators
 - Complete measurements started by physicists
 - Tune accelerator within guidelines
 - Practice routine measurements
- Frequent commissioning team meetings
 - 08:00 (7 days/week), 16:00 (M-F)
 - Controls Deputy manages Software releases

Organizational foresight

- Support group involvement in hardware:
 - Specification Development
 - Installation
 - Checkout
 - Commissioning
- Natural transition to Maintenance & Repair

Control System support

- Controls group provides infrastructure
 - EPICS, Network and IOC support
- High-level Applications minimal for start-up
- Heavy use of Matlab_R (The MathWorksTM)
 - Commissioning Physicists
 - Operators
 - Internal training
 - Controls group provides support
 - Training for Ops in EPICS, EDM screens

Operator Matlab GUI

LCLS Klystron Complement

Update Last update: 08-Apr-2010 22:35:38 Help -> Logbook

20	21	22	23	24	25	26	27	28	29	30
	-35.2	-35.3	-35.0	-35.1	0.0	-0.0	0.1	0.1	-31.2	30.5
1	1	1	1	1	1	1	1	1	1	1
2	2	2	2	2	2	2	2	2	2	2
3	3	3	3	3	3	3	3	3	3	3
4	4	4	4	4	4	4	4	4	4	4
5	5	5	5	5	5	5	5	5	5	5
6	6	6	6	6	6	6	6	6	6	6
7	7	7	7	7	7	7	7	7	7	7
8	8	8	8	8	8	8	8	8	8	8

Klystrons ON in L2: 25 Klystrons ON in L3: 45

History

Start Date (def. last 24 Hours) Show difference 08-Apr-2010 17:30:07

End Date (def. current)

WARNING! Experts only!

Flexibility

- Compromise between flexibility & discipline
 - Allow exploration by system experts during Commissioning
 - Tighter configuration control for operators during User runs
- Add simple diagnostics when schedules slip
 - Changing priorities for support groups
- Ops take over routine tasks, Experts move on to the next challenge

Challenges Ahead

- Advertised X-ray availability 95%
 - Technical challenges
 - Aging infrastructure with Linac
 - Cultural challenges
 - Different Operational mindset than High Energy Physics Experiments
 - Weekly (almost) shutdown days, short work list
 - Availability 'budget' for each system
 - First user run achieved goal (96%)
 - Additional complexity coming – multiple users

Thank you for your attention

