

**WAO10**  
**April 12 – 16, 2010**  
**INTEC, KAERI, Korea**

# **Maintenance Strategy of the PEFP Proton Linear Accelerator**

**Dae-il Kim ([dikim@kaeri.re.kr](mailto:dikim@kaeri.re.kr))**

**PEFP, KAERI**

- I. What we have, what we have to do**
- II. 20-MeV experiences
- III. 100-MeV plans
- IV. Summary

# What we have

- **Facilities**

- 20MeV proton accelerator
- Auxiliary parts for the accelerator
- Electrical power station
- Cooling station



- **Experiences on 20-MeV machine**

- installation,
- operation,
- maintenance



**Electrical power system utilities**

**Klystron (RFQ)    Waveguide    Klystron (DTL)    Target Station Beam Profile**



**Ion Source**



**LEBT**



**3 MeV RFQ**




**20 MeV DTL**



**Cooling utilities**

# What we have to do

- Installation at Gyeongju site
  - Disassembly of 20MeV linac
  - Packing and transportation
  - Installation
- After installation,
  - commissioning
  - operation
  - maintenance



- I. What we have, what we have to do
- II. 20-MeV experiences**
- III. 100-MeV plans
- IV. Summary

# Installation

- Experience on the heavy but carefully treated parts
  - DTL tank
  - Alignment
  - Klystron
  - Supporting structure
  - Modulator




# Packing and Transportation

- Experience on the heavy but carefully treated parts
  - Klystron : Return of the spare klystron to factory
  - DTL tank (?) – DT alignment




# Packing and Transportation

- Inspection of parts inside oil tank after the delivery
  - find to the damaged components



# Maintenance Statistics




# DT Replacement

- Reason


- Electromagnet failure at tank 3 HE / tank 4 LE side end plate
- Vacuum leakage at tank 4 / 15th drift tube
- On line replacement of the DT

- Check after replacement

- Field profile variation  $< 1\%$
- Resonant frequency compensation using wall temperature  $< 2$  deg. C



Drift tube replacement




Field profile before and after replacement

# Vacuum System – Commissioning stage

## • Vacuum system components of 20 MeV Proton Linear Accelerator

Pump	Comp.	Model	Pumping speed	Seal	Flange	No.
Scroll Pump	Varian	Triscroll 300	250L/s	Viton O-ring	NW25	5
	Iwata	ISP-500B	500L/s	Viton O-ring	NW40	3
TMP	Leybold	T1600	1600L/s	Copper	CF250	1
	Osaka	TG1300MCAB	1300L/s	Copper	CF200	2
	Varian	TV301 NAV	280L/s	Copper	CF8"	4
NEG Pump	Saes getters	CapaciTorr B 1300-2 MK5	1300L/s	Copper	CF8"	6
Ion Pump	Varian	Vaclon Plus 300	300L/s	Copper	CF8"	8



**At first,  
we mainly used the TMP for DTL tank**

# Vacuum System – Operation stage

- Change of the vacuum system operation from commissioning stage (2007)
  - TMP fails
  - Regular maintenance of the scroll pump
- Operation method
  - At initial evacuation, use a TMP (1 TMP/DTL tank)
  - At normal operation,  
use ion pumps as main pump (2 ion pump/DTL tank)  
gate valve close, turn off the TMP



**TMP:**  
Blade broken




**Scroll pump:**  
Replace of tip seal and bearing

# Electrical Power Station

- 22.9kV, 8MVA capacity
- VCB at the electrical power station
  - 8 years since manufacture
  - Coronal discharge at the VCB (June, 10, 2007)
- The number of permitted operation is within the limit, but the old causes problem



**VCB and its bus bar**



**Newly installed one**




**FRP barrier**

# High Voltage DC Power Supplies

- -100kV, 20A, <20J : 2 sets
- Arc energy limiting device : crowbar (RFQ), opening switch (DTL)
- Trips of the high voltage DC power supplies caused by
  - Malfunction of the protection circuit (DTL , 2005)
  - Crowbar trip due to the klystron arcs (RFQ, 2007~ 2008)  
: high voltage connectors of the inside and outside the oil tank

	2005	2006	2007	2008	2009	2010
Number of Trip	30	5	18	13	-	-



**Change the circuit to optical (DTL case)**




**Change the connector and re-adjust the inside connector (RFQ case)**

**Replace the systems with modulator to check the modulator performance at 2009**

# Installation of the Modulator

- Valve direction of the cooling circuit
- After installation of the cooling circuit, we could not operate the cooling circuit
- The directions of the check valve and solenoid valve were reversed




**Seal**




**Strainer**



**Solenoid valve**




**Check valve**



**Flow  
meter**

# Installation of the Modulator


- Inspection and test for the finding of the strange pulse




- C-phase of the CH4 is the strange pulse
- Ch 1: HVCM output voltage, Ch2&Ch3&Ch4 : A&B&C phase current



- Test after exchange the IGBT board



- HVCM output voltage : 7.5kV
- SCR voltage : 150V
- pulse width : 100us/div



# Cooling System

- 2MW, 6000lpm, 5bar : 2 sets
- Need regular maintenance – pump, heat exchanger, de-ionizer
- Problem : water leakage occurs many times
  - DTL DT cooling line
  - Klystron oil tank
  - RF load cooling circuit



**Water leakage at klystron oil tank**



**Cleaning of the heat exchanger plate**



**De-ionizer filter**




**Leak from the RF load cooling line joint**

# Example of the Spare Parts

- Keep spare ignitron switches as a crowbar switch of the HVPS
  - Original one : glass sealed type
  - Spare parts : ceramic sealed type
    - : New but unused for 6 years
- There was a problem for the unused new ignitron
  - Vacuum degradation and lost of the high voltage hold off capability
  - Disadvantage of the ceramic sealed type
- Need policy to choose the proper number, and storage period of the spare parts



**Glass sealed type**



**Ceramic sealed type**

- I. What we have, what we have to do
- II. 20-MeV experiences
- III. 100-MeV plans**
- IV. Summary


# Scheduled Maintenance

- **Regular maintenance period**
  - August at summer season
  - Dec. ~ Jan. at winter season
- **Make maintenance list, and do as the list**
- **List examples**
  - Vacuum system
    - Scroll pump, ion pump regen., NEG regen.
  - High voltage components
    - Insulation oils, silica Gel, keep clean
  - Cooling system
    - Grease, heat exchanger plate, DI system
  - Alignment of the system

- **Prepare spare part to reduce the down time**
  - **Disadvantage : Many important parts should be imported**
  - **Need to decide the number of spare part**
  - **Need to consider the unused period**
  - **Need to consider the delivery time**
  - **Need to consider the possible rental service**
  
  - **It is necessary for us to get advice from other experienced lab.**
  
- **Set up the possible fault scenarios and install MPS**
  
- **Long delivery items**
  - **Klystron**
  - **Modulator**
  - **etc.**

# Example of the MPS

- **Modulator**
  - 105kV, 5.8MW peak, 9% duty, 1.5ms long, 60Hz
- **CO2 system of the modulator as MPS**
  - Thank to the recommendations from the SNS



# Example of the Spare Parts

- Spare part list of the modulator
  - Proposed by the manufacturer
  - Decide items, number based on the strategy

Description	Price	Quatity	Delivery Time	Dynapower	Vendor
IGBT Switchplate Assembly				o	
Rogowski Coil Main					
IGBT, 1200A,3300V					o
IGBT Driver Board				o	
IGBT Fibler Optic Cables					o
IGBT gate bypass cards					
Modulator Differential Line Driver					
HV Boost Transformer				o	
Twinax Cable Terminations					
Twinax Cable Terminations					
Rogowski Integrator Box					
Oil Filter					o
Fan Filter					
Oil Pump Motor, 1 1/2 hp, 3500RPM					o
Safety Enclosure Fan					o
Oil Level Switch					o
3Ph 30A, Y Female Recepticle					
3Ph 20A, Y Female Recepticle					
3Ph 20A Y Male Recepticle					
Dessicant Breather Assembly					
Rectifier Card Assembly				o	
Energy Storage Capacitor				o	
IGBT bypass 10 uF 4kV caps				o	
IGBT 10 uF 2kV caps				o	
1800 pF 160 kV resonating caps					
900 pF 160 kV resonating caps				o	
500 pF 180 kV output caps				o	
50 kV resonant rectification caps				o	
.03 uF doubler caps				o	
DSP Control Chassis				o	
Dynamic Fault Detection Chasis				o	
HV connector assemblies				o	
Switchplate Handling and Installation fixture					

**HVCM unit**

Description	Price	Quatity	Delivery Time	Dynapower	Vendor
FUSE, 1.00A, 250V					o
FUSE, 200E AMP, 5.5KV					o
PILOT LIGHT, AMB					o
PILOT LIGHT, GRN					o
DIODE, 1010A, 5600V, DISC, 58MM					o
THYRISTOR, 2100A, 4200V, DISC, 7.7MM					o
H/F GATE DRIVE, 6 PUL, REV				o	
FIRING CKT LOGIC, 6/12 PLS				o	
INTERFACE, ZFCT				o	
REGULATOR, SWTCHR, REV B MO				o	
CURRENT IMBALANCE DETECTOR				o	
ISOLATOR, DIFF, HIGH PRECISIONRE				o	
H/F GATE DRIVE, 6 PUL, REV D 10K				o	
FUSE, 7.00A, 250V					o
SWCH, THRM, L-185, NC RED					o
SWCH, THRM, 356F, NC,PEPI					o
XFMR, CNTR, 500VA, 3300:110,50/60				o	
VALVE, BALL, 1-1/4, UNION, CPVC					o
METER, DIG PAN, 3-1/2, 20VDC					o
CNTR, 200A, 6.6KV, SF6,110VAC COIL					o
CURR SENS, 500A					o
ISOLATOR, DIFF, HIGH PRECISION RE					o
BRACKET, MOUNT, 1INCH					
VARIATOR, 1700VRMS, 6000J, BB					o
CAP, 0.82MFD, 3300VDC					o
RES, OHM, 15.00 190W, NON-IND					o
PROG CNTL, SLC500, POWER SUPPLY					
PROG CNTL, SLC500, PROCESSOR					
PROG CNTL, SLC500, 7 SLOT RACK					
PROG CNTL, SLC500, 12KFLASH					
PROG CNTL, SLC500, 16 AC IN, 120V					
PROG CNTL, SLC500, 8NO, 3A/120VAC					
PROG CNTL, SLC500, 16 RLY OUT					
PROG CNTL, SLC500, 8DC IN, SINK					
MOUNTING BOARD, 4 POSITION					
INPUT MOD, 5V LOG, 2.5-2.8Vin					
CNTR, 400A, 5KV, 120/230/50/60/DC					o
HT EXCH, W/A, 5291CFM, 3HP					o
SWCH, FLOW, 1.25 BODY, 20GPM					o
PWR SPLY, +/-15V, 1.5A, CA SE BB					o
FUSE, 15A, 250V					o
FUSE, 4.50A, 250V					o

**SCR unit**

- **We experienced on**
  - transportation
  - installation
  - operation
  - maintenance

**in the 20 MeV proton linear accelerator**
  
- **We will plan**
  - make maintenance list, and do as the list for scheduled maintenance
  - prepare spare part to reduce the down time

**for the unscheduled maintenance**

  - consider to buy the spare part
  - set up the possible fault scenarios and install MPS

**in the 100 MeV proton linear accelerator**