


FLASH Operation at DESY

From a Test Accelerator to a User Facility



Michael Bieler

FLASH Operation at DESY

WAO2012, SLAC, Aug. 8, 2012

Vocabulary

DESY: **D**eutsches **E**lektronen-**S**ynchrotron, Hamburg, Germany

TTF: **T**ESLA **T**est **F**acility

TESLA: **T**eV **E**nergy **S**uperconducting **L**inear **A**ccelerator

FLASH: **F**ree Electron **L**aser in **H**amburg



Content

The History of FLASH

TTF as a linear collider testbed

TTF operation

TTF becomes FLASH

FLASH user operation

Difficulties for Operators

Conclusion



The History of FLASH

1994: The **TESLA** project requires superconducting rf cavities for a TeV-scale linear collider.

TESLA Test Facility: A 500 MeV testbed for TESLA.

1997: **TTF** reaches 16.7 MeV/m with superconducting cavities

1998: **TTF** tunnel extended, first undulators in the tunnel

2000: First lasing @ 110 nm


2003: Extension from 100 m to 260 m, TTF becomes **FLASH**

2005: **FLASH** becomes a user facility, lasing at 25 nm

A test facility becomes a user facility.



The History of FLASH




The Future of FLASH

2012: FLASH running as

- a user facility, 4.1 – 50 nm
- a testbed for XFEL (component tests, diagnostics, control system, etc.)
- as a testbed for machine studies (Seeding, ...)

2013: FLASH will be upgraded to FLASH II



TTF as a linear collider testbed

TESLA **T**est **F**acility was a test facility:

- Components running at their limits
- Components from different vendors or collaborators
- Different kinds of the same component
(BPMs, current monitors, klystrons, modulators,...)
- Only the backbone of a control system
- Different integration of components into the control system
- Different levels of application software
- Different levels of documentation



TTF operation

Goals of TTF operation:

- High accelerating gradients
- Component tests for a linear collider

Mode of TTF operation:

- Separate control room
- Separate control system
- Separate operators (scientists and students)



TTF becomes FLASH

TTF was an ideal testbed for the SASE mechanism

- 200 MeV beam energy
- high current, pulsed, laser driven gun

1998: Conversion into a SASE FEL

- Chicanes for bunch compression (no 3rd harmonic cavity)
- More beam energy
- Better diagnostics
- Undulators
- Lots of Research and Development

The TTF VUV SASE FEL was born
(But it took years to get it running)


2000: First lasing @110 nm



TTF becomes FLASH

2003: Extension from 100 m to 260 m, TTF becomes FLASH


- longer tunnel, space for more accelerating modules
- energy upgrade over the years, 3rd harmonic cavity
- 1200 MeV reached in 2010




FLASH user operation

2010: 4.12 nm wavelength (well within the ‘water window’)


- FLASH is used for fundamental research




Original Foil



Reconstruction
from the diffraction
pattern of one shot



Diffraction pattern
of the first shot



Diffraction pattern
of the second shot

FLASH user operation

FLASH schedule:

User runs (3 – 5 weeks)

interleaved with

Accelerator studies
and FEL studies
(2 – 7 weeks)

FLASH
Schedule 2012-2013

week	date	schedule	goal
52	26.Dec - 1.Jan		
2012			
1	2.Jan - 8.Jan	FLASH commissioning	
2	9.Jan - 15.Jan		
3	16.Jan - 22.Jan		
4	23.Jan - 29.Jan		
5	30.Jan - 5.Feb	Accelerator studies	
6	6.Feb - 12.Feb		
7	13.Feb - 19.Feb		
8	20.Feb - 26.Feb	FEL studies	
9	27.Feb - 4.Mar		
10	5.Mar - 11.Mar		
11	12.Mar - 18.Mar		preparation user run
12	19.Mar - 25.Mar	User Run	
13	26.Mar - 1.Apr	Block 1	
14	2.Apr - 8.Apr		
15	9.Apr - 15.Apr	FEL studies	Survey
16	16.Apr - 22.Apr		
17	23.Apr - 29.Apr		preparation user run
18	30.Apr - 6.May		
19	7.May - 13.May	User Run	
20	14.May - 20.May	Block 2	
21	21.May - 27.May		
22	28.May - 3.Jun		
23	4.Jun - 10.Jun		
24	11.Jun - 17.Jun	Maintenance	rt gun exchange G4.2 -> G4.1
25	18.Jun - 24.Jun		vacuum work, dismount bypass
26	25.Jun - 1.Jul		
27	2.Jul - 8.Jul		
28	9.Jul - 15.Jul		
29	16.Jul - 22.Jul	Maintenance	vacuum work, survey
30	23.Jul - 29.Jul	FEL studies	
31	30.Jul - 31.Jul		
32	6.Aug - 12.Aug		preparation user run
33	13.Aug - 19.Aug	User Run	
34	20.Aug - 26.Aug	Block 4	
35	27.Aug - 2.Sep		
36	3.Sep - 9.Sep		
37	10.Sep - 16.Sep	FEL studies	
38	17.Sep - 23.Sep	Accelerator studies	
39	24.Sep - 30.Sep		preparation user run
40	1.Oct - 7.Oct	User Run	
41	8.Oct - 14.Oct	Block 5	
42	15.Oct - 21.Oct		
43	22.Oct - 28.Oct		
44	29.Oct - 4.Nov		
45	5.Nov - 11.Nov	FEL studies	
46	12.Nov - 18.Nov		preparation user run
47	19.Nov - 25.Nov	User Run	
48	26.Nov - 2.Dec	Block 6	
49	3.Dec - 9.Dec		
50	10.Dec - 16.Dec		
51	17.Dec - 23.Dec		
52	24.Dec - 30.Dec	Maintenance	



FLASH user operation

FLASH accelerator studies and FEL studies:

Performed by experts with a little help from some experienced operators.

FLASH user runs:

Performed by operators with a little help from some experts.



Difficulties for Operators

**Questions of a storage ring operator
on his first day at an FEL:**

First turn steering all day long?

Closed orbit? Closed bumps?

Betatron Tunes?

Where are the resonances?

Beam Energy, RF-Phases?

Not constant? Not known everywhere?

Dark Current?

What's that?

Bunch length?

Who cares?



Difficulties for Operators

Problems of a storage ring operator at an FEL:

Every slight change at the injector spoils the beam in the undulator section.

Every change in the energy distribution changes the beam optics.

Every change of RF-phases spoils the bunch length.

Dark current from the gun must not reach the undulator section.

Feedbacks, feedbacks, feedbacks....

Orbit, energy, peak current



Difficulties for Operators

Problems of a storage ring operator at an FEL:


Which tuning strategy works today?

**Many tuning parameters (like luminosity tuning),
but some can totally destroy SASE.**

The SASE effect is less robust than luminosity.

**Most lumi parameters have
a Gaussian distribution,**

**many SASE parameters
are steep peaks.**



Conclusion

FLASH had (and in parts still has) a lot of childhood diseases.

Parts of FLASH were never meant to be a user facility.

FLASH was (and in parts still is) a testbed.

The level of automation and feedbacks is not optimal.

Operators were not part of the FLASH crew from the beginning.

(Some) Storage ring operators have a hard time with an FEL.

**Operators are performing routine user operation now
(but still need help for e.g. wavelength changes).**



Conclusion

“FLASH performance is too much operator dependent”

(from our funding agency)

Operator Training!

Automation of Procedures!

Feedbacks!

(LCLS has 16 feedbacks running)

