

User Interface of operation status and beam permit system for beam service at KOMAC



Young-Gi Song, Sung-Yun Cho, Jae-Ha Kim, Hyeok-Jung Kwon

Korea Multipurpose Accelerator Complex, Korea Atomic Energy Research Institute., Gyeongju, Korea

Corresponding author: ygsong@kaeri.re.kr, phone: +82-54-750-5512

Linac & Beamline Operation

- Started user beam services from July 22, 2013.
- Proton beams delivered to TR23, TR101, TR102, and TR103.



Features of KOMAC 100MeV linac




- 50 keV Injector (Ion source + LEBT)
- 3 MeV RFQ (4-vane type)
- 20 & 100 MeV DTL
- RF Frequency : 350 MHz
- Beam Extractions at 20 or 100 MeV
- 5 Beamlines for 20 MeV & 100 MeV

Output Energy (MeV)	20	100
Max. Peak Beam Current (mA)	1 ~ 20	1 ~ 20
Max. Beam Duty (%)	24	8
Avg. Beam Current (mA)	0.1 ~ 4.8	0.1 ~ 1.6
Pulse Length (ms)	0.1 ~ 2	0.1 ~ 1.33
Max. Repetition Rate (Hz)	120	60
Max. Avg. Beam Power (kW)	96	160


- Accelerator division : 21 people
- Control (3), Nuclear, Electrical, Mechanical, ...
- Operated in weekly-based schedule through a yearly plan
- Beam service: Monday 13:00 ~ Friday 18:00
- Operators/shift
- 1 for accelerator
- 2 days a month as operator
- Beam Service : 2 for beam service in target room

Control System & Main Control Room

- Integrated the local system such as VME, PLC, SOM board with EPICS
- Linux-based system except some diagnostic systems
- Different Network: Machine network, Timing network, Interlock network
- EPICS Channel Archiver : operation data management
- Development software: EPICS, Python, Linux (petalinux), vxWorks



Configuration of KOMAC control system



- Center of operation for linac and beamline
- Operations performed by an integrated operations group in a single control room during commissioning or machine studies periods.
- Improve efficiency by allowing a single operator crew to monitor and control linac and beamlines.




- Personnel Safety Interlock System : shielding door control
- access control, interlock status
- Key box
- automatic beam service preparation
- Control consoles designed with enough flexibility to allow most accelerator programs to be operated from any location in the control room.
- DCS : utility control system
- Radiation monitor system
- Beam tuning system
- Alarm monitor

Beam Permission and Interlock

KEY BOX : for beam ready




Conceptual design





Simple state transition diagram

To minimize human error



Target room by key box

- Component status monitor : including vacuum pressure and gate valve, rccs, magnet, rf, modulator
- Assign flag value by component and a key value for target room selection
- For beam start, refer to the flag value, MPS, and PSIS



MPS



Machine Interlock

Interlock Box

