

Workshop for Neutrino Programs with facilities in Japan  
Aug 3, 2015 @Tokai-mura

# J-PARC Accelerator

- achievement and future upgrade -

Tadashi Koseki

Accelerator Laboratory, KEK  
J-PARC Center, KEK&JAEA


# Contents

1. Status of accelerator operation and achievement
2. Mid-term upgrade plan
3. Long-term plan
4. Summary

1. Status of accelerator operation and achievements
2. Mid-term upgrade plan
3. Long-term plan
4. Summary



# History of beam delivery to the MLF

• as of 3<sup>rd</sup> of June 2015




# New front-end system of the J-PARC linac

During the 2014 summer shutdown period, the front-end system of the linac was replaced to increase the peak current to 50 mA.




Beam study results in October, 2014



New front-end system in the tunnel.


# Demonstration of 1 MW-eq. beam

2015/1/10



## BLM signals @ collimator & arc sections


Mainly from foil scattering during injection




The anode power supplies of the rf power amplifiers is reinforced in the 2015 summer shutdown periods.

After the reinforcement, we will increase beam intensity for user operation toward 1-MW.

# History of MR beam power



Delivered beam power is 3




Total number is > 1.1x10<sup>21</sup> POT as of June 3.

# Slow extraction operation in April and June, 2015

After the long shutdown for 1 year and 11 months due to the radioactive material leak incident, beam operation resumed for users in the hadron experimental facility.

April 9, 2015 - June 26, 2015



# High Intensity beam study in June 2015


- at the present betatron tune (22.40, 20.75)-

Trial with

- 2<sup>nd</sup> Harmonic rf 30 kV
- Intra-bunch FB during Acceleration
- Resonance correction with trim Q and S


Extracted beam : 1.92e14 ppp

(372 kW eq. at the repetition of 2.48 s cycle)



Beam loss distribution

~ 800 W in total





- User operation with ~ 380 kW can be available soon.

- It is confirmed that design beam power of 750 kW can be almost achieved at the future high-repetition of 1.3 s.



# High Intensity beam study in June 2015 (cont'd)

- at the new betatron tune area -

## Horizontal tune survey at 3 GeV



## Vertical tune survey at 3 GeV




- ① 3<sup>rd</sup> Integer resonance correction ( $3Q_x=64$ ) by Trim-Sext.
- ② Larger tune spread and crossing integer resonance ( $Q_x=21$ )

# High Intensity beam study in June 2015 (cont'd)

- at the new betatron tune (22.239, 21.310) -

High power trial of 30 GeV acceleration with two bunches



Extracted beam : 6.82e13 ppp (132 kW eq.)

	Beam loss [Watt]	
INJ(K1+K2+K3+K4)	144	7.43e+11
P2 --> +90ms	241	1.00e+12
P2+90ms --> +120ms	31	1.30e+11
P2+100ms ---> EXT		1.83e+11

Total beam loss ~ 420 W



Near future tunable knobs to reduce the beam loss:  
Injection kicker, BxB feed-back,  
2nd harmonic cavity, VHF cavity, etc.

Bunch number	repetition period (sec)	Beam power (kW)	Beam loss (kW)	Notes
1	2	132	0.42	measurement
2	8	530	1.7	estimation
3	8	1000	3.2	estimation

**The MR has capability to reach 1MW with the high repetition rate operation.**

1. Status of accelerator operation and achievements
2. Mid-term upgrade plan
3. Long-term plan
4. Summary

# Mid-term plan of MR

**FX:** The high repetition rate scheme is adopted to achieve the design beam intensity, 750 kW. Rep. rate will be increased from ~ 0.4 Hz to ~1 Hz by replacing magnet PS's, RF cavities and some injection and extraction devices.


**SX:** Parts of stainless steel ducts are replaced with titanium ducts to reduce residual radiation dose. The beam power will be gradually increased toward 100 kW watching the residual activity.



JFY	2014	2015	2016	2017	2018	2019	2020
	Li. current upgrade		New PS buildings				
FX power [kW] (study/trial)	320	> 360	400	450	700	800	900
SX power [kW] (study/trial)	-	33 - 40	50	50-70	50-70	100	100
Cycle time of main magnet PS	2.48 s					1.3 s	
New magnet PS	R&D	Large scale 1 <sup>st</sup> PS		Mass production installation/test			
High gradient rf system		Manufacture, installation/test					
2 <sup>nd</sup> harmonic rf system		R&D, manufacture, installation/test					
VHF cavity	R&D						
Ring collimators		Add.collimators	Add.collimators (3.5kW)				
Injection system		Kicker PS improvement, Septa manufacture /test					
FX system		Kicker PS improvement, LF septum, HF septa manufacture /test					
SX collimator / Local shields			Local shields				
Ti ducts and SX devices with Ti chamber	Beam ducts	ESS					

# New power supplies for 1 Hz operation

## Large scale PS for bending magnets and quad. magnets in arc sections




Two large converters and large capacitance for energy recovery, symmetric power module circuit


The R&D history:

- (1) Proof of principle by a desk-top PS (2012)
- (2) R&D of the small prototype PS (2013)
- (3) R&D of the middle prototype PS (2014)

## - R&D results of the middle scale prototype PS -




Self-learning control system



Power recovery by C-bank

# R&D of new power supplies for 1 Hz operation (cont'd)

## *Small scale PS for Quad. Magnets in straight section and sextupole magnets*




Diode rectifiers, two 1kV choppers are connected in series, symmetric power module circuit


It is possible to build with the combination of existing products.

The model PS system was tested using the real sextupole magnet network.

### Current ripple at 30 GeV



Present IGBT-PS



The new PS

**Mass production can be started in JFY2016 if the budget request is approved by the government.**


## Plan of PS mass production

JFY	2015	2016	2017	2018
New buildings for new power supplies		← D4,D5,D6 →	■ ■ ■ ■ ■ ■ →	
Large PS (10) ( B (6), Q (4) )			← B (3) → ← Q (2) →	← B (3) → ← Q (2) →
Middle PS (1) ( Q(1) )	← Leading PS for mass-production →			
Small PS (9) ( Q (6), S (3) )		← Q (6) →	← S (3) →	
Cooling water system		← D4,D5,D6 →	■ ■ ■ ■ ■ ■ →	
Installation & tuning			← →	

# High impedance rf system


A new type of the magnetic alloy (MA) core, FT3L(made by Hitachi Metal), is adopted to increase shunt impedance of the rf cavity. The core is processed by annealing with magnetic field.

Comparison of field gradient of rf cavities for hadron rings.




Performance of cavities depends on core materials: ferrite and MA.

J-PARC already achieved very high field gradient.




Comparison of characteristics of large size cores



# RF system for high repetition operation

## Configuration of rf cavities



Before Replacement

After Replacement

	2013	2014	2015	2016	2017	2018
	<i>Li 400 MeV</i>	<i>Li 50mA</i>				<b>MR 1.3-sec operation</b>
<b>Present FT3M cavities</b>	9	8	4	0	0	0
<b>New FT3L Cavities</b>	0	1	5	9	9	9
<b>New FT3L 2<sup>nd</sup> cavity</b>	0	0	0	0	2	2
<b>Available voltage</b>	315 kV	355 kV	485 kV	602 kV	602 kV	<b>602 kV</b>
<b>(2<sup>nd</sup> Harmonic)</b>	(35 kV)	(70 kV)	(70 kV)	(70 kV)	(70 kV)	<b>80 kV</b>
<b>Number of cavity cells</b>	27	29	36	43	43	43+8(2 <sup>nd</sup> )


Required voltage: 280 kV(~2017), 540 kV(2018~)

# Injection and FX septum systems

New injection septum magnet I and FX low field septum for the high repetition rate operation have been manufactured and now tested.



Injection septum magnet I



FX low field septum magnet

New injection septum:

- Stable (low vibration)
- Small leakage field  $\sim 10^{-4}$   
(the current septum :  $4 \times 10^{-3}$ )

Eddy current type is adopted to the new FX low field septum

- Small Power Consumption (possible at low cooling capacity)
- Small Leakage Field  $\sim 10^{-4}$   
( the current type septum :  $10^{-3}$  )
- Stable (low vibration)
- Thin Septum Thickness  $\sim 7$  mm  
(the current septum : 9.5mm)

They will be installed in the 2015 summer shutdown.

1. Status of accelerator operation and achievements
2. Mid-term upgrade plan
3. Long-term plan
4. Summary

# Feasibility of the RCS


Injection beam parameters:

Energy : 400 MeV

Peak current : 50 mA~100 mA

Pulse length: 0.5 ms

Chopper-beam on duty : 0.53



RCS intensity	Loss	Loss power at 25 Hz
1.0 MW	~0.3%	400 W
1.1 MW	~0.3%	440 W
1.2 MW	~0.3%	480 W
1.3 MW	~0.3%	520 W
1.4 MW	~0.3%	560 W
1.6 MW	~0.5%	1067 W
1.8 MW	~0.7%	1680 W
2.0 MW	~1.5%	4000 W

RCS collimator limit ~4 kW

→ RCS has a feasibility to operate 2 MW

- Linac 100 mA/0.5 ms (50 mA/1.0 ms) operation is required.  
R&D of ion source / long pulse operation of linac
- The rf system should be replaced to compensate a heavy beam loading.
- The collimator capability should be upgraded to get a margin for the beam loss.
- Activation downstream of the charge exchange foils should be reduced.

....

# Future proton driver for long-baseline neutrino experiment

The maximum beam intensity is **limited by the physical aperture** of the MR.

The scenarios for achieving mult-MW beam for neutrino experiment are now under discussion.

## 1. Booster ring for the MR (emittance damping ring)

The BR with an extraction energy  $\sim 8$  GeV, is constructed between the RCS and the MR



## 2. Proton linac for neutrino beam production

( Construction site may not be the Tokai campus)

- Linac with an beam energy  $> 9$  GeV
- The MR is operated only for the SX users



# The 8-GeV booster ring

## Beta & Dispersion for 1-superperiod



Injection energy 3 GeV  
 Extraction energy 8 GeV  
 Circumference 696.666 m  
 Superperiodicity 4  
 Transition gamma  $\sim 15$  GeV  
 Collimator Aperture  $126\pi$ .mm.mrad  
 Physical Aperture  $189\pi$ .mm.mrad

## Phase plot @ inj.(3GeV) & extr.(8GeV)



8 GeV injection in the MR using new septa&kickers

RCS : 1.6 MW  
 MR > 2.6 MW  
 RCS : 2 MW  
 MR > 3.2 MW

# Proton Driver in the KEKB Tunnel


As the post-Super KEKB projects in KEK

KEKB tunnel:

- fourfold symmetric configuration.
- Circumference:  $\sim 3$  km
- Straight section: beam acceleration  
 $200 \text{ m} \times 4 = 800 \text{ m}$
- Arc section: beam transportation to  
the next straight section.  
 $550 \text{ m} \times 4 = 2200 \text{ m}$

Subjects:

- Feasibility of 9 GeV proton linac in  
straight sections of 800 m.  
 $\Rightarrow$  High acceleration field is required.  
 $\Rightarrow$  SC accelerator is essential.
- Beam transport at Arc sections.



# SC Cavity for 2<sup>nd</sup> to 4<sup>th</sup> Straight Sections

For the acceleration in the 2<sup>nd</sup> to 4<sup>th</sup> straight section, the ILC cavity is adopted.

## ILC cavity



Shape	ellipse
RF frequency	1.3 GHz
# of cells per cavity	9
Quality factor	$> 1 \times 10^{10}$ @ 2K


## ILC cryomodule



KEK has rich experience and know-how of ILC cavity and cryomodule fabrication.

## Average gradient ( $E_0$ )

Yield of usable gradient of 185 ILC cavities as received (European XFEL)




Average **usable** gradient:

**(26.2 ± 7.5) MV/m**

With the expectation of further R&D, we set the  $E_0$  to **30 MV/m**.

# Outline of the Proton Driver using ILC Cavity


- Outline of acceleration :
  - 1.2 GeV in 1<sup>st</sup> straight.
  - 3.3 GeV in 2<sup>nd</sup> straight.
  - +2.9 GeV in 3<sup>rd</sup> and 4<sup>th</sup> straight.  
 $3.3 + 2.9 \times 2 = 9.0 \text{ GeV}$
- Peak current : 100 mA (pulse)
- Beam duty : 1 %
- Beam power :  
 $9000 \text{ MeV} \times 0.1 \text{ A} \times 1 \% = 9 \text{ MW}$
- $\beta_g$  of SC cavities :
  - 2<sup>nd</sup> straight :  $\beta_g = 0.93$
  - 3<sup>rd</sup> and 4<sup>th</sup> straight:  $\beta_g = 1.0$
- Normalized RMS emittance
  - Transverse :  $0.30 \pi \cdot \text{mm} \cdot \text{mrad}$
  - Longitudinal :  $0.37 \pi \cdot \text{MeV} \cdot \text{deg}$




# Configuration of the cryomodules

## The 2<sup>nd</sup> straight section:

- Doublet lattice with SC quadrupole magnets.
- 4 SC cavities ( $\beta_g = 0.93$ ) are in each cryomodule.
- 27 cryomodules are placed in the section.  
7.1 x 27 = 192 m




## Beam profile at the 2<sup>nd</sup> straight section




## The 3<sup>rd</sup> and 4<sup>th</sup> straight section:

- Singlet lattice with a SC quadrupole magnet.
- 8 SC cavities ( $\beta_g = 1.0$ ) are in each cryomodule.
- 16 cryomodules are placed in each straight section.  
12.0 m x 16 = 192 m



## Beam profile at the 3<sup>rd</sup> and 4<sup>th</sup> straight section



R&Ds are necessary : Higher gradient SC cavities, High power target, Horn...

# Summary

## Status and operation summary:

- Achieved beam power in user operation :
  - 500 kW for MLF users
  - 360 kW and 33 kW for the T2K experiment and HD users, respectively.
- High power demonstration :
  - 1 MW eq. beam is achieved in the RCS
  - 132 kw eq. beam with two bunches in the MR ( It corresponds 530 kW with 8 bunches)
  - It shows the MR has a capability to reach beam power  $\sim 1$  MW with the high rep rate operation.

## The MR mid-term plan :

- The design power of 750 kW for the FX, and 100 kW for the SX will be achieved in 2018-2019 after the replacement of main magnet power supplies.
- The MR will reach 1 MW with the new power supplies after 2020.

## Long-term plan :

- Simulation shows the RCS has a capability to increase beam power  $\sim 2$  MW.
- To achieve multi-MW beam power for neutrino experiment, the 8-GeV booster, the 9-GeV SC linac are now under discussion.